



SVEUČILIŠTE U ZAGREBU
GRAĐEVINSKI FAKULTET
UNIVERSITY OF ZAGREB
FACULTY OF CIVIL ENGINEERING

Design project of the family house P+P+2K made from crosslaminated timber (CLT) and the BIM of the house

MASTER THESIS

Student: **Domagoj Stamac**

Supervisor: **Prof. Vlatka Rajcic, PhD**

Zagreb, the 18th of February, 2021

The master thesis is written under the guidance of supervisor prof. Vlatka Rajcic, PhD. The thesis is the intellectual property of the University of Zagreb and the Faculty of Civil Engineering. All the content and rights belong to the author and the publisher.

Content

1.	Introduction	1
2.	Cross-laminated timber (CLT)	4
2.1.	Development and production of cross-laminated timber (CLT)	4
2.2.	Characteristics of cross-laminated timber	11
2.2.1.	Characteristic resistance of the CLT element to actions perpendicular to the plane	11
2.2.2.	Characteristic resistance of the CLT element to in-plane actions.....	13
2.2.3.	Recommended characteristic values of resistance of CLT elements	16
2.2.4.	Resistance of CLT elements to ultimate limit state (ULS)	16
2.2.5.	Resistance of CLT elements to the serviceability limit state (SLS)	19
2.2.6.	Fire resistance of CLT.....	21
2.2.7.	Seismic resistance of CLT.....	22
2.2.8.	Sustainable development and CLT	23
3.	Project task of family house.....	25
3.1.	Technical description.....	25
3.2.	Load analysis.....	28
3.2.1.	Dead load	28
3.2.2.	Live load	30
3.2.3.	Snow.....	32
3.2.4.	Vjetar.....	35
3.3.	Static calculation of CLT panels	48
3.3.1.	Model description and input parameters.....	48
3.3.2.	Verification of surface elements on ultimate limit state (ULS).....	59
3.3.3.	Verification of surface elements on serviceability limit state (ULS) deflections	95
3.3.4.	Verification of the floor panel for vibration and fire resistance	98
3.4.	Dynamic calculation and seismic analysis	108
3.4.1.	Modal analysis and modal response spectrum.....	108
3.4.2.	Seismic calculation	116
3.5.	Verification of member elements on ULS and SLS	120
3.5.1.	Beams and columns	120
3.5.2.	Beams of glass panels 60x60 mm	125
3.5.3.	Columns 130x130 mm	130

3.5.4.	Beams 130x320 mm.....	138
3.6.	Stability of CLT panels	156
3.7.	Design of glass panels according to ULS and SLS	161
3.7.1.	Preliminary design of the panels.....	161
3.7.2.	Calculation according to plate theory.....	166
3.8.	Design of connections	179
3.8.1.	X-One connectors for CLT panels.....	179
3.8.2.	Connection of beams 130x320 to the CLT walls and other beams.....	192
3.8.3.	Connection of beams 130x320 to columns 130x130.....	198
3.8.4.	Connection of CLT panels to the concrete slab on the ground floor.....	201
3.8.5.	Connection of vertical CLT panels.....	206
3.8.6.	Connection of vertically continued wall CLT panels	210
3.8.7.	Beam and CLT wall panel connection	212
3.8.8.	Connection of floor and wall CLT panels to each other in a plane	214
3.8.9.	Connection of CLT floor panels to beams	218
3.8.10.	Connection of the columns to the concrete slab on the ground floor	222
3.8.11.	Connection of CLT wall panels with concrete slab on the ground floor	224
3.9.	Transport and logistics of materials	229
3.9.1.	Transport to the construction site	229
3.9.2.	Transport on the construction site	231
3.10.	BIM model and drawings.....	234
1.	Axonometric view of the building (southwest side)	235
2.	Axonometric view of the building (southeast side)	235
3.	Axonometric view of the building (northwest side)	235
4.	Axonometric view of the building (northeast side)	235
5.	Ground plan of foundation strips	235
6.	Basement floor plan.....	235
7.	Ground floor plan.....	235
8.	Floor plan of ground floor ceiling panels	235
9.	Floor plan of 1st Floor	235
10.	Floor plan of ceiling panels in 1st Floor	235
11.	Floor plan of 2nd Floor.....	235
12.	Floor plan of ceiling panels in 2nd Floor	235

13.	Section 1.....	235
14.	Section 2.....	235
15.	Section 3.....	235
16.	Southeast facade.....	235
17.	Southwest facade.....	235
18.	Northwest facade.....	235
19.	Northeast facade.....	235
4.	Conclusion.....	236
	Literature	238
	References	239